



NOTES

- A. ALL WORK TO CONFORM TO ODOT CONSTRUCTION AND MATERIAL SPECIFICATIONS LATEST REVISION UNLESS OTHERWISE SPECIFIED.
- B. ITEM 407 TACK COAT, SHALL BE REQUIRED WHEN 10 DAYS HAVE ELAPSED BETWEEN BITUMINOUS PAVEMENT LIFTS UNLESS OTHERWISE SPECIFIED BY THE ENGINEER. APPLICATION RATE IS .10 GALLON PER SQUARE YARD.
- C. NO CONCRETE PAVEMENT WILL BE ACCEPTED.
- D. SIDEWALKS NOT REQUIRED IN INDUSTRIAL ZONING.
- E. ALL BUTT JOINTS SHALL BE SEALED WITH PG64-22 WITHIN 24 HOURS AFTER PLACEMENT OF ITEM 404.

ITEM	DESCRIPTION	ARTERIAL	COLLECTOR		LOCAL
			COMM. & IND.	RESIDENTIAL	
I	RIGHT-OF-WAY	80'	60'	60'	50'
II	B\B CURB	57'	41'	37'	34'
III	SIDEWALK WIDTH	4'	4'	4'	4'
IV	APRON WIDTH	6.5'	4.5'	6.5'	3.5'
V	ITEM 404	1-1/4"	1-1/4"	1-1/4"	1-1/4"
VI	ITEM 402	1-3/4"	1-3/4"	1-3/4"	1-3/4"
VII	ITEM 301	7"	7"	4"	3"
VIII	ITEM 304	2-4" LIFTS	2-4" LIFTS	2-3" LIFTS	2-3" LIFTS

VILLAGE OF
ADA
CHOICE
ONE
ENGINEERING

TYPICAL SECTIONS AND PAVEMENT COMPOSITION

REVISIONS:
MARCH 2001
JULY 2007

DATE
APPROVED:
MAY 1997

PAGE No.
300-2