



**NOTES**

- A. CENTERLINE OF METER TO BE NO MORE THAN 36" FROM THE FLOOR.
- B. METER MUST BE MOUNTED HORIZONTALLY.
- C. METER BOLTS, NUTS, AND METER FLANGE GASKETS PROVIDED BY THE VILLAGE.
- D. METER SETTING ASSEMBLY TO BE SOLDERED COPPER OR BRASS PIPING.
- E. ALL PIPING TO BE THOROUGHLY SUPPORTED.
- F. THE VILLAGE IS NOT RESPONSIBLE FOR MAINTENANCE OF INSIDE PLUMBING.
- G. PROVIDE 2 APPROVED BACKFLOW PREVENTERS OF EQUAL SIZE TO THE METER OPERATED IN PARALLEL. THE VILLAGE HAS THE OPTION TO REDUCE THE NUMBER OF BACK FLOW PREVENTERS UPON REQUEST.
- H. VILLAGE WILL PROVIDE LOCK FOR BYPASS VALVE.
- I. METER BYPASS TO BE SAME SIZE AS METER.
- J. BACKFLOW PREVENTERS SHALL BE TESTED AFTER COMPLETION BY OHIO CERTIFIED BACKFLOW PREVENTER TESTER AND PAPERWORK PROVIDED TO WATER DEPARTMENT.
- K. A MINIMUM OF 2 1/2 PIPE DIAMETERS OF STRAIGHT RUN OF PIPE OR EQUIVALENT FULL OPEN COMPONENTS IS REQUIRED UPSTREAM AND DOWNSTREAM OF THE METER OR STRAINER FLANGES. FULL OPEN FLOW COMPONENTS MAY CONSIST OF: STRAIGHT PIPE, FULL OPEN GATE VALVES, BYPASS TEES AND CONCENTRIC REDUCERS.

# 1 1/2" AND 2" METER WITH BYPASS

|            |           |
|------------|-----------|
| REVISIONS: | DATE      |
| 8-1-1999   | APPROVED: |
| 3-1-2000   | MAY 1997  |
| 3-1-2003   | PAGE No.  |
| 3-1-2009   | 800-13    |